### **Concrete Batch Controllers**

TABLE OF CONTENTS

1280® FlexWeigh Systems ...... 320

Decumulative/Accumulative Batcher

## 1280® FlexWeigh Systems

Decumulative/Accumulative Batcher



#### **Standard Features**

- · Powered by 1280 Enterprise Series indicator
- · Large 12-in color touchscreen display
- · Remote batching through web server integration
- Front panel control switches and emergency stop
- · Automatic or manual batching modes
- · Configurable from two to five scales (one to two cement scales, and one to three material bins)
- Up to four admixes (bottled or direct)
- · Manual entry of moisture compensation percentage
- Metered water controlled by onboard DIO
- Import/export databases via USB, Revolution® or Interchange software
- Configurable batch transaction ticket
- Storage for 1,000 transactions, 1,000 mix designs, 500 customers
- · Available with English or Spanish operation and in imperial or metric measurements

#### **Options**

- Desktop stand
- Sun visor

#### Part Number/Price

Part #	Description	Price
208907	Decumulative batcher	\$15,950.00
216733	Accumulative batcher	Consult
212392	Sun visor	\$500.00
212234	Desktop kiosk stand	\$450.00

#### **Specifications**

#### Power:

100 to 240 VAC; 50/60 Hz

#### **Excitation Voltage:**

 $10\pm0.5\ VDC$ 

 $16 \times 350$  ohm or  $32 \times 700$  ohm load cells per A/D card

#### **Analog Signal Input Range:**

-60 mV to 60 mV

#### **Analog Signal Sensitivity:**

 $0.3\,\mu\text{V/graduation}$  minimum at 7.5 to 120 Hz 1.0 µV/graduation recommended

#### A/D Sample Rate:

7.5 to 960 Hz, software selectable

#### Resolution:

Internal: 8,000,000 counts Display: 1,000,000

#### System Linearity:

± 0.01% full scale

#### **Communication Ports:**

Port 1 & 2: Full duplex RS-232 with CTS/RTS, RS-422/485

Baud Rate: 1200 to 115200 Port 3: USB 2.0 Device (Micro)

USB Host: (2) Type A Connectors max 500 mA

Ethernet: Wired 10/100 Auto-MDX Ethernet: Wireless 802.11 b/g/n 2.4GHz

#### On board:

Selectable filters: Three stage, adaptive or damping Embedded Linux® OS 8 GB eMMC (system use) 1 GB DDR3 RAM 460 MB onboard database (SQLite) storage

Up to 32 GB micro SD card

#### Display:

Twelve-inch, 1280 × 800 pixel, 1,500 NIT

#### Temperature Range:

Certified: 14 °F to 104 °F (-10 °C to 40 °C) Operating: -4 °F to 131 °F (-20 °C to 55 °C)

#### Rating/Material:

Painted mild steel enclosure NEMA Type 4; IP66

#### **Dimensions:**

 $20 \times 20 \times 8$  in

#### Warranty:

Two-year limited

#### **EMC Immunity:**

EN 50082 Part 2 IEC EN 61000-4-2, 3, 4, 5, 6, 8, 11

# CONCRETE BATCH CONTROLLERS

# 1280® FlexWeigh Systems Decumulative/Accumulative Batcher

Front Panel Switches				
	Decumulative Batcher	Accumulative Batcher		
Auto/Manual	х	х		
E-Stop	х	x		
Conveyor Start/Run*	х	x		
Bin 1*	х	х		
Bin 2*	х	х		
Bin 3*	х	х		
Cement 1*	х	х		
Cement 2*	х	х		
Water*	х	х		
Admix 1*	х	х		
Admix 2*	х	х		
Admix 3*	х	х		
Admix 4*	х	х		
Aggregate Hopper		х		
Cement Hopper		х		

<sup>\*</sup> Available in Manual Mode

Outputs				
	Decumulative Batcher	Accumulative Batcher		
Conveyor Start/ Run	x	x		
Alarm/Horn	х	х		
Bin 3 Vibrator	х			
Bin 3 Feed	х	х		
Admixture 1 Fill/Feed	x	х		
Admixture 1 Discharge	x	x		
Admixture 2 Fill/Feed	x	x		
Admixture 2 Discharge	x	х		
Admixture 3 Fill/Feed	х	х		
Admixture 3 Discharge	х	х		
Admixture 4 Fill/Feed	х	х		
Admixture 4 Discharge	х	x		
Bin 1 Feed	Х	Х		
Bin 2 Feed	Х	Х		
Cement 1 Feed	Х	Х		
Cement 2 Feed	Х	Х		
Water Feed	Х	Х		
Bin 1 Vibrator	Х	X		
Bin 2 Vibrator	Х			
Cement 1 Air	X	x		
Cement 2 Air	Х	х		
Dust Collector 1	Х	х		
Dust Collector 2	х	Х		
Aggregate Vibrator		х		
Cement Vibrator		х		
Aggregate Air		х		
Water Discharge		х		
Aggregate Gate Open		х		
Aggregate Gate Close		x		
Cement Gate Open		x		
Cement Gate Close		x		

Inputs				
	Decumulative Batcher	Accumulative Batcher		
Admixture 1 Bottle Empty	x	x		
Admixture 1 Pulse	x	x		
Admixture 2 Bottle Empty	x	x		
Admixture 2 Pulse	x	х		
Admixture 3 Bottle Empty	х	x		
Admixture 3 Pulse	x	x		
Admixture 4 Bottle Empty	x	x		
Admixture 4 Pulse	x	x		
Manual Mode	x	x		
Air Pressure OK	x	x		
E-Stop	x	x		
Water Meter Pulse	x	x		
Conveyor Running	x	x		
Water Gate Limit Switch		x		
Aggregate Gate Limit Switch		х		
Cement Gate Limit Switch		x		

