

Specifications

Full Scale Capacity: 20,000 lb, 5 lb increments

Racks and Gates:

Constructed of three-inch steel main tubes; two-inch steel support tubes Two end swing gates with latch (gates swing outward from scale)

Load Cells:

Single tool steel S-beam

Warranty:

Two-year limited warranty on the weighbridge Two-year parts and electronics warranty

Approvals:

NTEP 94-126

- · Bolt-on racks and swinging gates
- Durable X-Lug or X-Plank rubber floor over a steel I-beam deck (foundation slab required)
- Solid 48-inch kick panel rack
- Solid 48-inch kick panel swinging gate
- Spring-loaded latch on swinging gates
- Rugged all-weather powder paint
- Scale collapses for shipping
- Factory assembly at no charge

Part Number/Price

Part #	Description	Inside Dimensions (L × W)	Outside Dimensions (L × W)	Est. Weight	Price
132879	Multiple animal scale - mechanical lever system with single cell	12 ft 2 in × 6 ft 6 in	13 × 9 ft	5,550 lb	Consult
132881	Multiple animal scale - mechanical lever system with single cell	14 ft 1 in × 6 ft 6 in	15 × 9 ft	6,040 lb	Consult
132882	Multiple animal scale - mechanical lever system with single cell	16 ft 1 in × 6 ft 6 in	17 × 9 ft	6,650 lb	Consult
132883	Multiple animal scale - mechanical lever system with single cell	18 ft 1 in × 6 ft 6 in	19 × 9 ft	7,210 lb	Consult

Price does not include instrumentation

Options/Accessories

•		
Part #	Description	Price
215306	482-AG Indicator, LCD display, 115 VAC	Consult
169478	920i indicator with group software 12V DC	Consult
167689	920i indicator with group software, 115V	Consult
156758	AC adapter for 920i weigh center or indicator	Consult
23113	TM-U295 ticket printer	Consult
15547	Blunt end cable for printer to indicator	Consult
71630	Tickets for TM-U295 prints 4.25 × 7 in	Consult
130961	Factory scale assembly	Consult
189536	Solar panel retrofit kit	Consult





X-Plank rubber floor X-Lug rubber floor